



Executive Engineer (Elect.)
CONSTRUCTION WING

PRASAR BHARATI
(BROADCASTING CORPORATION OF INDIA)

Telefax: 2493 6094
Telephone : 2492 1590
Email : ccwelect@rediffmail.com

All India Radio & Doordarshan, Block 7-10, Basement, New Bldg, TV Centre, Worli, Mumbai #
No. : EEE/CCW/NIQ/2011-2012/836 Dated:11/10/2011

NOTICE INVITING QUOTATION

Item rate sealed quotations are hereby invited on behalf of the President of India by the undersigned, from the Contractors for following on **17-10-2011** and will opened on same day at **3.30 P.M** in the presence of authorized representatives of the questioners present, if any. The undersigned has the right to reject any or all the quotations without assigning any reasons.

Name of Work Construction of Building for Guest House at Ahmadabad (Gujarat)
(Sh-S/I/T/C/ of Split A/C)

<u>Sr.No</u>	<u>Description of Item</u>	<u>Qty</u>	<u>Rate</u>	<u>Unit</u>	<u>Amount</u>
As per attached schedule					
Total					

Conditions:

1. No advance payment will be given.
2. Nothing will be paid extra.
3. The time limit for the work is 01 (One) Months.
4. Rates should be inclusive of all taxes nothing extra shall be paid on any account.
5. The work is to be executed as per CPWD Specification.

To,
M/s

EXECUTIVE ENGINEER (ELECT.)
CCW: AIR : MUMBAI

Copy to:


1. The Superintending Engineer (Elect), AIR,6th Floor
NBH, Sansad Marg, New Delhi-110011
2. The Assistant Engineer (Elect.), CCW, AIR, Rajkot.
3. The AAO, CCW(E), AIR, Mumbai.
4. Notice Board.
5. Spare copies.

EXECUTIVE ENGINEER (ELECT.)
CCW : AIR : MUMBAI.

SCHEDULE OF WORK

Name of Work : Construction of Building for Guest House at Ahmedabad (Gujarat)
(Sh-S/I/T/C/ of Split A/C)

It. No	Description of items	Qty	Unit	Rate	Amount
1	Supplying, installation, testing & commissioning of following size, type airconditioner units suitable to work on 230V, 1 Ph, 50 Hz electric supply along with wall mounted indoor unit, weather proof outdoor unit with suitable size M. S. Powder coated stand, accessories like cooling coil, thermostat, control panel with remote facility, indicator, hand shutoff valves, suitable size copper refrigeration piping with necessary size PUF sleeved insulation, control and power cables from indoor unit i/c first charge of refrigerent gas after satisfactory leak testing and trial run etc. as required				
	a) 1.5 Tr.-3* Rating, Voltas Make, Model - Vertis Gold or Similar superior approved make.)	3	Each		
2	Extra for suction and discharge copper tubing with necessary thermal insulation, supports, clamping with PVC drain piping with necessary sloping ect. As required.	24	Mtr.		


Executive Engineer (Elect)
CCW, AIR, Mumbai