



PRASAR BHARATI
(BROADCASTING CORPORATION OF INDIA)
OFFICE OF THE ASSISTANT ENGINEER (ELECTRICAL)
CIVIL CONSTRUCTION WING : ALL INDIA RADIO
SHYAMLA HILLS : BHOPAL - 462013

Phone : 0755 2660713

e-mail: aeccwairbpl@rediffmail.com

No. 4(5)/AEE/BPL/CCW/AIR/2011-12

Dated: 30-8-2011

NOTICE INVITING QUOTATION

Sealed quotations are hereby invited on behalf of the President of India for the work mentioned below from the contractors of PWD/BSNL/MTNL/P&T/MES/Railway/MP State PWD so as to reach this office on or before 12-9-2011 up to **3.00 p.m.** and the same will be opened on same day at **3.30 p.m.** in the presence of the Contractors or his authorized representatives. The undersigned reserves the right to accept/reject any/all quotations without assigning any reasons.

Name of Work: Renovation/Modification of Doordarshan Maintenance Centre building for Doordarshan at AIR Campus Sagar (MP) (SH: Providing of Bracket light CFL fittings on the corners of the DMC building)

S.No.	Description of item	Quantity	Rate	Unit	Amount
	AS PER SHEDULE ATTACHED				

Total ₹

Issued to:- _____

Terms & Conditions of work:-

1. Work is to be carried out as per CPWD specifications.
2. No T & P will be issued by the Department.
3. Payment shall be made only after completion of work from the office of EE(E),CCW,AIR,Nagpur.
4. Rate quoted should be inclusive of all the taxes like sale tax, VAT, octroi, work contract tax, service tax etc.
5. Time to complete the work will be 15 days from the date of issue of work order.

(RAJINDER SINGH)
ASSISTANT ENGINEER(ELECT)

The above quotations may be seen on www.tenderhome.com & www.allindiaradio.org.

Copy to:-

1. The Executive Engineer (Elect), CCW, AIR, Nagpur.
2. The Executive Engineer (Civil), CCW, AIR, Bhopal.
3. The Station Engineer, All India Radio, Bhopal
4. The Assistant Engineer (Civil), CCW, AIR, Bhopal
5. Junior Engineer (Elect) CCW, AIR, Bhopal.
6. Notice Board of Sub-Division Office, CCW, AIR, Doordarshan Kendra Bhopal.
7. M/S Sugal infotech Pvt. Ltd., 6/35 W.E.A, Karol Bagh, New Delhi - 110005 for uploading the quotation on their website.
8. Superintending Engineer, New Broadcasting House, All India Radio, New Delhi-110001, for uploading the quotation on AIR website.

Assistant Engineer (Elect)

SCHEDULE OF WORK

Name of Work: Renovation/Modification of Doordarshan Maintenance Centre building for Doordarshan at AIR Campus Sagar (SH: Providing of Bracket light CFL fittings on the corners of the DMC building)

S.No.	Description of Item	Quantity	Unit	Rate	Amount
1	Supplying, installation testing and commissioning of 1 x 36 watt CFL bracket light deep drawn MS housing with epoxy powder coated finish and acrylic cover inclusive of, lamp connection etc complete on the existing bracket as required.(Make: Crompton Paramount cat no.SCE1336 or as per the make approved by the department)	4 Nos	Each		
2	Supplying & fixing of 32mm dia x 1.5 metre long GI pipe (medium class) bracket for mounting of fluorescent/HPSV/HPMV street light fitting on pole/wall including bending the pipe to the required shape, 40mm x 3mm flat iron clamps and wiring with 1.5 sqmm weather proof/PVC wire and painting the flat iron with primer and finish paint etc as required.	4 Nos	Each		
3	Supplying and fixing weather proof cable IP65 with plane walls thermoplastic junction box of size 200mm x 160mm x 98mm deep having front opening cover i/c providing and fixing 2nos 4way brass connector strip 15amps per way superior quality 1no. 6amps SPMCB complete and fixing the box with suitable size of MS clamp with painting , sign	5 Nos	Each		

	writing, etc as required.(Make Hansel cat no. 8250 or the make as approved by deptt.)				
4	Supplying and Laying of one number 2x6 sqmm PVC insulated and PVC sheathed/XLPE aluminium conductor armoured U.G. power cable of 1.1 KV grade confirming to relivent IS with upto date ammendments in the following manner				
a)	In the existing RCC/HUME/STONEWARE/METAL pipe as required.	5 M	Meter		
b)	In the existing masonry open duct as required.	10 M	Meter		
c)	Fixing on surface as required.	68 M	Meter		
5	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a)	2 x 6 sqmm	15 Nos	Each		
6	Providing and fixing 6 SWG dia GI wire on surface or in recess for loop earthing alongwith existing surface / recessed conduit/submain wiring/cable as required.	83 M	Meter		

7	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/recess, complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, interconnections, phosphatized and powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
a)	4 way double door	1 Nos	Each		
8	Supplying & fixing of 5 amps to 32 amps rating 240 volts 'C' series, miniature circuit breaker of following poles in the existing MCB DB complete with connections, testing and commissioning etc as required.				
a)	Single Pole and neutral	1 Nos	Each		

TOTAL

ASSISTANT ENGINEER (ELECT)