



**PRASAR BHARATI
(BROADCASTING CORPORATION OF INDIA)
DIRECTORATE GENERAL; ALL INDIA RADIO
(PLANNING & DEVELOPMENT UNIT)**

FNo. 27/12/1(16) Silchar/2006-D(TD/FM)

Specification for Supply, erection, testing and commissioning (SETC) {of 16 Panel VHF FM Antenna, RF Cable, RF Rigid Lines & Accessories as per AIR specification for VHF FM Transmitters set up } (SITE- Silchar)

{Specification no: SETC 16 P Antenna, RF Cable /16 / Silchar/December/2006- D(TD/FM)}

{ Total no of pages: 33 }

Date of approval :

CONTENTS

SECTION 1.0 TECHNICAL REQUIREMENTS

: (Page number 3)

SECTION 2.0 GENERAL SPECIFICATION

: (Page number 4 to 10)

SECTION 3.0 TECHNICAL SPECIFICATIONS

3.1 16 PANEL VHF FM ANTENNA : (Page number 11 to 17)

3.2 RF CO-AXIAL CABLES & DEHYDRATORS

: (Page number 18 to 19)

3.3 RF RIGID LINES & ACCESSORIES : (Page number 20 to 21)

SECTION 4.0 INSPECTION

: (Page number 22 to 24)

SECTION 5.0 SCHEDULE OF (SUPPLY)

SECTION 5.1 Schedule of Supply at Silchar

: (Page number 25 to 28)

SECTION 6.0 SCHEDULE OF ERECTION, TESTING & COMMISSIONING

SECTION 6.1 Schedule of Erection, testing & commissioning { of 16 panel VHF FM Antenna, RF Cable, RF Rigid Lines & Accessories } **at Silchar**

: (Page number 29 to 33)

N.B. :

- 1. The Tenderer shall submit schedule of material /requirement of SETC without price as above in Section 4.0 to Section 6.0 of AIR Specification (two bid system i.e. technical bid and commercial bid).**
- 2.Each statement of this specification has to be complied with & supported by printed literature/data sheets from the manufacturer of the equipment by the tenderer, without which tender will be considered incomplete & is liable to be rejected. The tenderer should make a detailed offer.**
- 3.All the technical details , Schematic drawings and schedule of requirement/material must be submitted and enclosed with the tender by the tenderer and failing which the tender is liable to be rejected.**
- 4. The tenderer shall submit the tender offer to AIR in the format given below.**

Sr No. of AIR Spec. Section wise& Clause wise	Details of AIR Spec.	Performance figures of equipment, schematic drawing Nos. and Model No.	Compliance Yes/NO	Ref to tender page No.	Remarks
Section 1.0					
Section 2.0					
Section 3.0					
Section 4.0					
Section 5.0					
Section 6.0					

- 5. Tenderer shall quote the rate / cost of individual items in the tender offer while submitting the offer for spares.**
- 6. The tenderers shall fill up their name in CAPITAL LETTERS, full address with pin code , phone number, fax number, e-mail address and with their full signatures , failing which the tender shall be liable to be rejected.**

SECTION 1.0 TECHNICAL REQUIREMENTS NEW FM STATION)

(SITE- Silchar)

S.No	Project	16 Panel Antenna	*RF Co-axial cable Length (M) & Size	RF rigid lines& accessories required	Reference to SECTION of AIR Specification
1.	Silchar Please refer Note No.I	1 No.	1x160 M (3-1/8") Please refer Note No.II	Yes	5.1/ 6.1

- Note: I. The order will be placed as per the site condition.**
II. Exact length will be intimated at the time of placement of order
III. TV Tower height - 150 M

SECTION 2.0 GENERAL SPECIFICATION

SECTION 2.0

Note : Please refer tender documents for general term and conditions of contract for SETC works including all the commercial aspects like ;
Packing and Packing List, Insurance and Marine Risk etc., Guarantee, Payment terms, Penalty/Compensation for Delay, Damages and Liabilities, Time Period and Extension for Delay , Foreclosure of Contract due to Abandonment or Reduction in Scope of Work, Cancellation of Contract in Full or Part, Recovery of Security Deposit, Performance Guarantee, Indian Electricity Rules ,Unsatisfactory Workmanship, Damages Incurred During Erection , Tenderer Liable for Damages, Defects, Recovery of Compensation, Ensuring Payment and Amenities, Labour Laws to be Complied by Tenderer, Minimum Wages Act Compliance, Tenderer to Indemnify Government against Patent Rights, Return of Surplus Material, Employment of Technical Staff and Employees, Release of Security Deposit, Safety Code, insurance from manufacturer's works/factory to site etc **i.e. in totality** .

GENERAL SPECIFICATIONS :

All equipment and items of SETC as per AIR specification shall be used for round the clock continuous operation without any interruption in VHF FM broadcast service at various AIR stations.

Each statement of this specification has to be complied with & supported by printed matter from the manufacturer of the equipment by the Contractor.

1.0 SCOPE:

Supply, erection, testing and commissioning (SETC) of Antenna System comprising of 16 Panel VHF FM Antenna , RF Cable, RF Rigid Lines & Accessories as per AIR specification for VHF FM Transmitters set up.

The broad scope of above supply, erection, testing and commissioning (SETC) on FM Band-II Aperture are as follows:

1.1 16 Panel Four Bay VHF FM antenna as per Specification.

1.2 RF cable as per Specification .

1.3 RF Rigid Lines as per the specification.

2.0 For completion of the SETC all the items, fittings and accessories which are necessary for the setup , which may not have been specifically mentioned or which the Tenderer may not explicitly mention in the tender but all the same are necessary for the operation of the equipment shall be deemed to be included in the tender and shall be provided by the successful Tenderer without any additional

- payment by the Indentor . The full technical details and technical literature/ pamphlets shall be submitted by the Tenderer.
- 3.0 INSPECTION: Inspection will be as per detail given in Annexure I of AIR Specification by the representative of All India Radio at manufacturers works.
- Before giving the call for inspection to the Indentor, the Tenderer should satisfy themselves that the offered equipment etc. are as per the AIR Specification and approved drawings. Tenderer shall submit one set of complete performance figures as per ATP to the Indentor before giving call for inspection to the Indentor.
- Prior intimation for carrying out inspection and pre-despatch performance test as per ATP at works is to be given by the Tenderer to the indenter at least 6 weeks in advance.
- The total inspection period for each SETC shall be 2 working days (for 16 Panel VHF FM Antenna , RF Cable, RF Rigid Lines & Accessories). Expenses for inspection charges on account of providing of infrastructure are to be quoted separately. For AIR Inspecting Engineers expenses toward to and fro air journey, boarding, lodging etc. will be borne by All India Radio.
- 3.1 Acceptance Test Procedure will be submitted by the Tenderer within one month of placement of order in respect of all the equipment /items. This will include all tests so as to assess the performance of the equipment vis-à-vis all specifications .
- 4.0 The successful Tenderer shall supply within one month from the date of acceptance of the tender, 2 sets of complete design & drawing documents in respect of the setup for the approval of AIR. Tenderer should submit detailed design, complete drawings with full details as per the specification.
- 5.0 DESIGN & DRAWING DOCUMENTS :
(**Total 3 sets**)
{ SITE - Silchar }
After approval of all the design document and drawings of complete set up (as per the specification)
- The Tenderer shall send ,
one set of all above complete drawing documents to **site** i.e Installation officer / Superintending Engineer/ Station Engineer, All India Radio, concerned;
(TOTAL - 1 SET)
one set of the above documents to the Chief Engineer of the Zone (EZ) and
(TOTAL - 1 SET)
one set of the above documents to Director Engg.(Proj.), P&D Unit, DG, AIR, New Delhi-110001
(TOTAL - 1 SET)
i.e. in brief, 3 sets of such drawings and design document are required against SETC.
A soft copy of these documents on CD shall be provided to DE(Proj.), P&D Unit, DG:AIR, New Delhi by the Tenderer.

- 6.0 All the necessary measuring equipment and tools etc. required for completion of Erection of the project will be arranged by the Tenderer during SETC and no additional amount shall be paid on this account.
- 7.0 Supply , erection, testing and commissioning (SETC) of above “set-up” as per specification shall be done by Qualified Engineer at site.
- 8.0 The Tenderer should either be original equipment manufacturer or supply the equipment only from the original equipment manufacturer. Original manufacturers should have ISO certification for the manufacturing work and the documentary proof for all above are to be enclosed by the Tenderer with the Tender paper/documents.
- 9.0 The Tenderer may make a site visit before submitting the tender document.
- 10.0 DELIVERY PERIOD (FOR SETC):
- 10.1 SUPPLY, ERECTION, TESTING & COMMISSIONING: - 12 months from the date of placement of order .
- 10.1.1 The time period for erection, testing and commissioning shall be as per 10.1 (from the date of placement of order) however, Tenderer shall try to complete the project before the above period.
- 11.0 The Tenderer shall prepare the PERT chart of the total project activities and submit the same to Zonal Office and Director Engg (Project), P&D Unit, DG,AIR, New Delhi- 10001 after the placement of order and within one month.
- 12.0 All information submitted by the Tenderer & all markings, notes, designation on the design, drawing documents & associated write-ups shall be in "English language" only. All dimensions and units on drawings and all references to weights and measures and quantities shall be in metric units.
- 13.0 Complete printed technical information in support of compliance statement should be furnished with the tender to assess the full merit of the offer. The tender & the associated information should be submitted in duplicate.
- 14.0 Descriptive information giving complete details of each equipment offered . shall be given by the Tenderer.
- 15.0 Make, model and type of individual units along with printed technical details shall be given by the Tenderer.
- 16.0 The Tenderer shall make his own arrangements for temporary power supply, water etc. and for the storage of equipment / material including the safe custody at erection site from the start of work & up to completion of the project. All responsibility regarding above arrangements shall be of the Tenderer.

17.0 The Tenderer shall make his own arrangements for providing accommodation for his workmen at site.

18.0 The Tenderer shall make his own arrangements for the labour, skilled and unskilled.

The Tenderer should conform to all local State laws/Central laws and regulations amended up to date concerning labour and their employment as applicable. The insurance etc of the labourers shall be the responsibility of the Tenderer including any kind of pre /post action and consequences relating to above insurance etc.

19.0 Prior approval of the Indenter in writing, shall be obtained, if the Tenderer desires to sublet or assign any section of the work Such permission or consent shall not, however, absolve the Tenderer from his liabilities in this contract or any part thereof.

20.0 The Tenderer is required to submit details of his previous experience in similar type of project i.e. the capacity of their organizational set up for undertaking such work.

21.0 The Tenderer shall indemnify the purchaser, his employees and purchaser employees from any liability that may arise out of infringements of patents and copy rights associated with the design, fabrication, erection of any equipment etc.

22.0 Tenderer shall submit detailed Supply, erection, testing and commissioning schedule of equipment/requirement offered as per specification. This list should be in the same format as in the price bid minus the price.

23.0 HANDING OVER OF DETAILED MANUALS & DRAWING:

23.1 At the time of handing over, the Tenderer shall hand over technical manuals (for erection, testing, commissioning, Operation, maintenance & theory of operation manuals, fault diagnostics with a copy of the Inspection Report carried out at factory and performance measurement carried out at the time of commissioning on site) of SETC (16 Panel VHF FM Antenna , RF Cable, RF Rigid Lines & Accessories) after incorporating the necessary corrections / changes etc. during the SETC to the following . **(Total :6 Sets)**

23.1.1 DE (Projects), P&D Unit, DG: AIR, New Delhi with One soft copy on CD of all these manuals, drawings, instructions, performance measurements, amendments, etc.
one set for site- Silchar
(TOTAL- 1 set)

23.1.2 **Chief Engineer (East Zone): - one set for site - Silchar**
(TOTAL- 1set)

23.1.3 Site consignee - The Station Engineer

The Station Engineer, AIR, Silchar.
-- **one set** (Silchar)

23.1.4 At the time of handing over, the Tenderer shall also hand over technical manuals of 16 Panel VHF FM Antenna , RF Cable, RF Rigid Lines & accessories (for erection, testing, commissioning, Operation, maintenance & theory of operation, fault diagnostics with a copy of the Inspection Report carried out at factory and performance measurement carried out at the time of commissioning on site) manuals (after incorporating the necessary corrections/ changes, if any , during the SETC) to the following.

23.1.4.1 DE(Transmitter Maintenance), DG:AIR - 1 set

23.1.4.2 Technical Library, P&D Unit, DG:AIR - 1 set

23.1.4.3 Staff Training Institute (Technical) - 1 set

Total - 3 sets

24.0 In support of Tenderer's claim an "up-to-date" list of their customers alongwith complete set of detailed actual performance figures for SETC project similar to AIR Specification (duly certified by the customers) must be furnished alongwith the tender.

A supply record of similar SETC project power wise and year wise in the last 2 years for field proven and satisfactory operation may be enclosed. Names, Address, E-mail, telephone nos. and Fax numbers of customers must be indicated.

25.0 In case of 'kits' complete details of component that form part of kit should be spelled out/clearly given i.e. the details of the component/item offered in the kit including their part no. and quantities.

26.0 INFORMATION TO PRECEDE DESPATCH OF EQUIPMENT:

Following information should be supplied to Indentor and each of the consignees, prior to dispatch of equipment:

26.1 Detailed list of equipment under dispatch .

26.2 Photographs, detailed engineering drawings showing location/details of components in the various units and sub units with Item/part number marked thereon.

27.0 Tenderer shall take all the necessary safety precautions while carrying out the SETC work as per the relevant IS Standards in respect of all erection activities to

ensure the safety of the his employees and purchaser employees. Tenderer shall use proper and specified/recommended tools and safety devices and ladders etc during the erection of project.

- 28.0 All material to be used at site of work shall be got verified from the AIR representative authorized by Directorate before commencement of erection.
- 29.0 The Tenderer is required to undertake a pledge for providing prompt after sale service. In any case, the response shall be made available within 48 hours.
- 30.0 After completion of work the Tenderer shall remove dust, dirt, debris and leave the building/premises in a clean condition .
- 31.0 Confirmatory documentary evidence of the equipment that all the equipment as per the individual specification have been actually purchased /imported from the original manufacturers shall be submitted by the Tenderer.
- 32.0 Tenderer shall submit the following details which are required along-with tender to assess the full merit of the offer :
"Complete information, details, parameters and drawings as mentioned in specification and information required for Fixing/ Mounting the various Fixtures / Accessories are to be submitted with tender."
- 33.0 TRAINING (OPTIONAL) (At site): Tenderer will arrange training at site/place as decided by Directorate for 3 working days.
- 34.0 SUPPLY, ERECTION, TESTING AND COMMISSIONING :
The SETC {of 16 Panel VHF FM Antenna , RF Cable, RF Rigid Lines & Accessories as per AIR specification for VHF FM Transmitters set up}, shall be undertaken by the Tenderer in accordance with ATP and in conformity with the AIR Specification.
- 34.1 SUPPLY: Supply of 16 Panel VHF FM Antenna , RF Cable, RF Rigid Lines & Accessories etc. shall be as per SECTION 5.0 of AIR Specification.
- 34.2 ERECTION: 16 Panel VHF FM Antenna , RF Cable, Antenna Switch Frame / Panel, RF Rigid Lines & Accessories (as per SECTION 6.0) at site will be erected in the transmitter complex as per layout plan approved by AIR.
- 34.3 TESTING:
16 Panel VHF FM Antenna , RF Cable, RF Rigid Lines & Accessories and associated equipment are to be tested after the erection, after making all the initial checks including physical inspection and continuity checks of wiring/cabling etc. as per drawings. Only after satisfying that erection is fit for testing (without the application of RF power), the testing will be taken up with RF power in a sequential manner in respect of all the equipment. The testing will be undertaken by the Tenderer

as per standard practice followed by the manufacturer and in conformity with procedure laid down in ATP.

- 34.4 COMMISSIONING AT SITE: After erection and testing of the 16 Panel VHF FM Antenna, RF Cable, RF Rigid Lines & Accessories & accessories as per AIR Specification , for VHF FM Transmitters, performance figures/measurement for all parameters are to be taken by the Tenderer in the presence of AIR's representative as per ATP.

Field strength survey of actual 360° horizontal radiation pattern shall be carried out upto the threshold of 48 dBu i.e. minimum required signal strength for rural monophonic service by the Tenderer. The F.S. Survey shall also give the details of coverage corresponding to 74 dBu, 66 dBu, 54 dBu contours (Stereophonic service).

In brief, full antenna radiation pattern is to be got validated on site after commissioning.

The performance measurement of the 16 Panel VHF FM Antenna , RF Cable, RF Rigid Lines & Accessories along with transmitter and associated equipment will be taken at site as per the Acceptance test procedure (ATP) approved by AIR .

- 35.0 In case of any tender where unit rate of any item/items appears unrealistic, such tender will be considered an unbalanced and in case the Tenderer is unable to provide satisfactory explanation , such a tender is liable to be disqualified and rejected.

- 36.0 On acceptance of the tender, the name of the accredited representative(s) of the Tenderer who would be responsible for taking instructions from DG:AIR ,New Delhi-110001 or his authorized representative shall be communicated in writing to Indentor.

We hereby fully agree to the above GENERAL SPECIFICATIONS { of 16 Panel VHF FM Antenna , RF Cable, RF Rigid Lines & Accessories as per AIR Specification for VHF FM Transmitter in respect of site Silchar } .

Signature of Tenderer with date and seal

Full Name in CAPITAL LETTERS:

Full Address with PIN code in CAPITAL LETTERS:

Telephone No.:

FAX No. :

E-Mail:

Witness Signature:

Full Name in CAPITAL LETTERS:

Full Address with PIN code in CAPITAL LETTERS:

Telephone No.:

(PURCHASE SECTION)
P & D UNIT, DG :AIR

SECTION 3.0 TECHNICAL SPECIFICATIONS

3.1 16 PANEL VHF FM ANTENNA

Frequency of VHF FM Transmitter : ***.** Mhz
(exact frequency will be intimated at the time of placement of order).

16 PANEL FOUR BAY VHF FM ANTENNA

1.0 INTRODUCTION:

- 1.1 The FM Antenna is required for use with FM transmitter of All India Radio, in Typical , Heavy Rain Fall, Humid as well as Dry , Salt Air Laden environment & Desert Conditions (as the case may be as per site conditions). The Antenna will consist of 16 Panels and each side or face consisting of four bays(level) of Antennae Panels.

Each Bay (level or stage) shall consist of 4 panels, which will be mounted on each of the four faces of the tower; so as to obtain omni directional pattern. (Tower heights is given in Section 1.0 of AIR Specification).

- 1.2 The Power will be feed to the Antenna through single RF coaxial air dielectric Cable. The Antenna will be installed on a existing self-supporting tower. The FM aperture of tower will be of square cross-section of about 2500 mm x 2500 mm with Latticed Steel Structure . The tower shall also be having VHF TV Antennae in Band – I / Band–III and UHF TV Antennae in Band–IV / Band-V in addition to VHF FM Antenna in Band -II .

2.0 ELECTRICAL PARAMETERS:

- 2.1. Polarization : Circular.

- 2.2 Input impedance : 50 Ω (ohm) unbalanced ,each.
- 2.3 Frequency Range : 88 -108 MHz.
- 2.4 Return Loss :**
- 2.4.1 Return Loss : ≥ 26 dB over the Operating Frequency Range (88 -108 MHz)
- 2.4.2 Return Loss Value(dB) in Graph form over entire (88 -108 MHz) frequency range to be enclosed.
- 2.5 Power Rating : ≥ 40 KW
- 2.6 Downward beam tilt : Between [0.5 $^\circ$ to 1 $^\circ$] for entire Operating Frequency Range
- 2.7 Null filling : Required, 15%.
- 2.8 **Antenna gain** (with respect to half wave dipole) - (Antenna gain in all directions over entire frequency range of 88 - 108 MHz should be enclosed with the tender)
- 2.8.1 ≥ 5 dBd in the direction of minimum radiation .
(Gain figure is for each polarization i.e Horizontal & Vertical and which shall be given by the tenderer separately and antenna shall be circularly polarized as per 2.1).
- Note : Gain figure is to be submitted in dBd only i.e. with respect to half wave dipole.
- 2.9.1 No. of Vertical Panels : 4 Nos.(i.e. No. of Bays = 4)
{on each face of Square tower}
- 2.9.2 No of Panels per Bay : 4 Nos.
- 2.10 Spacing between panels: Actual distance to be intimated in tender and a drawing showing profile Erection of panels also to be forwarded.
- 2.11 Vertical Plane: Expected Pattern for 0 $^\circ$ to ± 90 $^\circ$ to be forwarded with tender.
- 2.12 Antenna panels feeding arrangements : Antenna system full details and detailed schematic drgs of the above proposed feeding system from transmitter output in the transmitter hall to antenna on the existing tower shall be submitted with tender by the Tenderer along with Power Dividers ,Rigid lines, branch feeder cables/ Distribution Feed Cables
- 2.13 Antenna Mounting details: The Antenna panels will be mounted on Square Face of a Steel Latticed structure of existing tower in the FM aperture . Cross sectional size of the Tower will be about 2.5 m x 2.5m. All the dipoles of each panel will be mounted

on a Reflector Panel.

2.14 Full Performance Details : Detailed drawings and data sheets are to be forwarded with Tender for the following.

2.14.1. Actual measured Field Radiation Pattern, for V&H vectors separately, for a similar Antenna supplied elsewhere.

2.14.2 Calculated & Predicted Radiation Patterns for Horizontal & Vertical Planes for entire Operating Frequency Range of 88 Mhz to 108 Mhz.

2.14.3 Return Loss Graphs for Single Horizontal & Vertical Dipoles of Antenna Panel; Pair of Horizontal & Vertical Dipoles of Antenna Panel & Full Antenna Panel.

2.14.4 Return Loss Graphs of Power Divider, & its each sub power divider network system along with insertion loss figures ---- are to be given.

2.14.5 Performance Tables are required to be attached for

2.14.5.1 Power & Voltage Ratings and Safety Factors.

2.14.5.2 Power Ratings & Attenuation for Distribution Feeder Cables.

2.14.5.3 Power Monitoring Unit Set up levels for Rigid Lines at FM Band II. (as applicable)

2.14.5.4 Peak voltage ratings.

3.0 Pressurisation System : Pressurisation in the entire Antenna System is must through out the chain including main RF Coaxial cable , power dividers, splitters, branch feeder, sub distributor cables, antenna dipoles or panels .The RF coaxial cables used for branch feeder, sub distributor cables and up to the antenna dipoles or panels shall be air dielectric :

Full details of test values and operating values are to be given by the Tenderer in accordance with standard practice followed/ manufacturer recommendations.

4.0 ANTENNAE INPUT CHARACTERSTICS:

4.1 Input Connectors : 3-1/8" power rating for input 40 KW with IEC 3-1/8"

5.0 MECHANICAL DETAILS : { For Entire Antenna Assembly }

5.1. Maximum Wind Speed : 180 km. / hour.

5.2 Weight of Antennae : ≤ 1800 Kg.

5.3 Wind Load : ≤ 3500 Kg

5.4 Vertical Antenna Aperture : ≤12, 000 mm

5.5. EXTERNAL MATERIAL : Panels / Dipoles will be made of stainless or Marine Brass
Power Dividers & Rigid feed lines will be made of Marine Brass or Copper .

End Connectors on Dipoles and Feed Cables will be of standard & reputable makes & their makes should be indicated in Tender. All electrical contacts must be silver

plated. Reflector Panels & clamps shall be constructed of hot dip galvanized M.S. material OR light weight alloy/ fiber reinforced materials . All fasteners will be of Stainless Steel or High Tensile non corrosive material.

5.6 INTERNAL MATERIAL: Inner lines of Dipoles will be of copper or Brass . All electrical contacts will be silver plated. All inners and bullets will be made of Beryllium copper and silver plated. Insulators will be made of high quality pure Teflon / PTFE.

6.0 All joints to be made completely air tight & water tight.

7.0 TEMPERATURE/RH: – 5° C to 55° C, & 95% , NC, Heavy rainfall area.

8.0 MOUNTING ARRANGEMENT : All the 16 panels will be fixed on vertical and horizontal supports available on the four faces of Tower. These supports may be of angle iron rails. Technical details are to be forwarded by the Tenderer.

9.0 INPUT CONNECTORS : To match with 3-1/8” EIA Flange connector.

10.0 ACCESSORIES : Antenna supply will be complete with Power Dividers, Rigid Lines, Distribution Feed Cables with matching End Connectors, Adaptors/ Reducers ; Clamps & Fasteners for Dipoles, Power Dividers and Reflector Panels etc. Full details, list and drawings to be forwarded with tender.

11.0 TECHNICAL DATA: Following technical details data and engineering drawings are to be submitted by the Tenderer.

11.1 LIGHTNING PROTECTION: Full Features for Lightning protection are to be provided.

11.2 Complete information, details, parameters and drawings as mentioned in specification and information required for Fixing/ Mounting the various Fixtures / accessories for the SETC set up are to be submitted with tender by the Tenderer.

11.3 Complete set of Engineering Drawings giving full details, Quantity & dimensions of Dipoles, Power Dividers, Rigid Lines, Distribution Feed Cables, Reflector panels & mounting Accessories and SETC system and complete list of items should be forwarded with tender.

11.4 Make, Model & Type of Rigid lines, Distribution Feed cables and Matching End Connectors as above should be given in tender.

11.5 Dead weight of Each Antenna Panel (Kg)with fully mounted Dipoles , Reflectors, Baluns & Screens. Individual weight (Kg)of Dipoles, Reflectors, Baluns, Screens & Power Dividers and all accessories separately and RF cable are also to be given in tender.

11.6 Wind Load of complete Antenna System with all 16 panels mounted on tower alongwith RF cable at 180 Km/hr as well as 198 and /216 Km/hr Wind speed should be given in the tender.

11.7 A write up giving working details and salient features of the Antenna system to be forwarded with tender.

11.8 Power handling capacity of following items shall be indicated in the tender document by the Tenderer:

11.8.1 Individual Dipoles

11.8.2 Feed cables

11.8.3 End connectors

11.8.4 Power dividers

11.9 One assembled Panel details to be indicated in tender.

11.10 Insertion loss (dB)figure from input point to the end of Distribution Feed cable shall also be indicated.

12.0 **Dead weight and wind load (Kg):** Full technical details for complete antennae system shall be submitted by the tenderer along with the tender in the format given below:

SNo.	Description	Dead Weight	Wind load	Wind load	Wind load	Wind load
		(Kg)	(Kg)	(Kg)	(Kg)	(Kg)
			At wind speed 216	At wind speed 198	At wind speed 180	At wind speed
1.	Single dipole					
2.	Single panel circularly polarized antenna					
3.	16 panels circularly polarized antenna					
4.	Antenna power dividers, distributors,					
5.	Antenna clamps					

	hardware etc.					
--	---------------	--	--	--	--	--

13.0 Continuous Average Power Rating (KW) etc. : Continuous Average Power Rating (KW) and full technical details for complete antennae system shall be submitted by the tenderer along with the tender in the format given below:

SNo.	Description	Continuous average power rating (KW)	Size	Gain Circularly polarization (dBd) *	Gain Horizontal polarization (dBd)*	Gain Vertical polarization (dBd)*	VSWR
1.	Single dipole antenna i.e. for horizontal or vertical polarization						
2.	Single panel circularly polarized FM antenna						
3.	16 panel VHF FM Circularly polarized antenna fully pressurized						
4.	antenna input main RF power divider /splitter (as per design of manufacturer)						
5.	main branch RF co-axial air dielectric feeder cables (as per design of manufacturer)						
6.	sub power dividers /splitters (as the case may be / as per design of manufacturer)						
7.	distributors RF co-axial air dielectric feeder cables(as the case may be / as per design of manufacturer)						

Note :* Gain figures must be submitted in dBd only i.e. gain with respect to half wave dipole .

14.0 GUARANTEE: Tenderer shall submit with his tender an undertaking to accept the following guarantees:

- 14.1 A guarantee that the equipment supplied will be in accordance with these specifications, varied only to the extent stated in his tender and agreed to in the contract.
- 14.2 A guarantee to make good within 30 days at his own expense any component which becomes defective under normal operating conditions within 18 months from the date of acceptance of the equipment at respective site.
- 14.3 A guarantee to supply all components for a period of 10 years from the date of acceptance of equipment at site, at rates at which these are being supplied by him to other customers & also should match prices of original manufactures of these components prevailing at the time.
- 14.4 If at any stage, during next 10 years, the manufacturer stops production of this model of equipment , he shall intimate All India Radio in advance to enable the later to stock the critical items
- 15.0 Inspection /Acceptance tests: will be carried out at the suppliers works as per Annexure -I . It will be the responsibility of the supplier to arrange equipment and instruments for inspection. Charges for inspection, if any, may be quoted separately.

SECTION 3.0 TECHNICAL SPECIFICATIONS

3.2 RF CO-AXIAL CABLE

RF CO-AXIAL AIR DIELECTRIC FEEDER CABLE, 3- 1/8"

- 1.0 RF coaxial air di-electric , Co-axial Feeder Cable of size (Nominal) 3- 1/8" (88-108 MHz)
- 1.1 Capable of handling ≥ 40 KW Average Power at around 40° C Ambient Temp
- 1.2 Attenuation ≤ 0.4 dB / 100M .
- 1.3 Impedance 50 ohm .

Actual Cable length will be intimated at the time of order however feeder cable length may be considered as tentative as given in SECTION 5.0 of AIR Specification.

2.0 All accessories associated with Feeder cable are to be provided as per details given below.

- 2.1 3 -1/8" EIA flange connectors - 2 nos .
- 2.2 3 -1/8" EIA flange Gas Pass connector-2 nos.
- 2.3 Hoisting stocking s,- 2 nos.
- 2.4 Earthing kits-3 nos.
- 2.5 Wall gland-1 no.
- 2.6 Cable clamps with nut, bolt washer (adjustable width) and associated accessories.
- 2.7 Any other accessories offered for the completeness - 1 Lot of the system (Item wise details of offered and included material , item & parts are to be given by the Tenderer).

3.2.1.1 Dehydrator with tubing & accessories :-- As per cable manufacturer's recommendation for ensuring required Pressurisation in entire RF Cable and Antenna System -- Chain for supplying dry air for Pressurisation -- for one RF feeder cable and Antenna system.

Qty -1 Set.

3.2.1.2 GUARANTEE: Tenderer shall submit with his tender an undertaking to accept the following guarantees:

- (i) A guarantee that the equipment supplied will be in accordance with these specifications, varied only to the extent stated in his tender and agreed to in the

contract.

- (ii) A guarantee to make good within 30 days at his own expense any component which becomes defective under normal operating conditions within 18 months from the date of acceptance of the equipment at respective site.
- (iii) A guarantee to supply all components for a period of 10 years from the date of acceptance of equipment at site, at rates at which these are being supplied by him to other customers & also should match prices of original manufactures of these components prevailing at the time.
- (iv) If at any stage, during next 10 years, the manufacturer stops production of this model of equipment, he shall intimate All India Radio in advance to enable the later to stock the critical items

3.2.1.3 Inspection /Acceptance tests: will be carried out at the suppliers works as per Annexure -I . It will be the responsibility of the supplier to arrange equipment and instruments for inspection. Charges for inspection, if any, may be quoted separately.

SECTION 3.0 TECHNICAL SPECIFICATIONS

3.3 RF RIGID LINES & ACCESSORIES :

RF COAXIAL RIGID LINES & ACCESSORIES FOR COMPLETENESS OF SYSTEM

1.0 Technical Specification of Rigid lines (50 Ohm)(88-108 MHz):

Sno.	Technical Parameter	1-5/8"	3-1/8"
1.1	Average Power Rating	≥ 15 KW	≥ 50 KW
1.2	VSWR	1.05:1.0	1.05:1.0
1.3	Attenuation	≤ 0.60 dB/100M	≤ 0.32 dB/100M
1.4	Ambient temperature	40°C	40°C
1.5	Inner Conductor Temp.	≥ 100 °C	≥ 100 °C
1.6	Peak Power Rating	275 KW	1100 KW

2.0 Complete erection material for connecting the output of each transmitter to input ports of Combiners such as rigid lines, elbows, unions and matching reducers, wherever

necessary to complete the erection for feeding to the Antenna and Dummy Load .

Complete erection material and accessories for connecting the output of transmitters to input ports of Combiner and combined output from the output port of Combiner to Input of following - such as rigid lines, elbows, unions, matching adaptors, reducers, where ever necessary to complete the erection - will also include the following items .

- 2.1 Any accessories offered for the completeness of the system (Items wise details of offered and included material , items & part are to be given by the Tenderer) - 1 Lot

[After taking into consideration the Note given on page 21]

Note: Following RF coaxial rigid lines /accessories are to be given by AIR. After completion of work , balance quantity , if any , will be returned by the tenderer to AIR immediately. However rate per number in respect of following RF coaxial rigid lines /accessories shall be quoted as “OPTIONAL ITEM” by the tenderer.

1. 3-1/8" rigid line - 12 M
2. 3-1/8" Elbows with inner and bullets - 12 nos.
3. 3-1/8" Couplings with inner and bullets - 20 nos.
4. 3-1/8" Field Flange with inners and bullets - 2 nos.
5. 3-1/8" to N Test Reducer - 1 no.
6. 3-1/8" to 1-5/8" reducer/adopter-2nos.
7. 1-5/8" to 7/8" reducer/adopter-2 nos.
8. 1-5/8" rigid line - 6 M
9. 1-5/8" Elbows with inner and bullets - 6 nos.
10. 1-5/8" Couplings with inner and bullets - 20 nos.
11. 1-5/8" to N Test Reducer - 1 no.

GUARANTEE: Tenderer shall submit with his tender an undertaking to accept the following guarantees:

- (i) A guarantee that the equipment supplied will be in accordance with these specifications, varied only to the extent stated in his tender and agreed to in the contract.
- (ii) A guarantee to make good within 30 days at his own expense any component which becomes defective under normal operating conditions within 18 months from the date of acceptance of the equipment at respective site.
- (iii) A guarantee to supply all components for a period of 10 years from the date of acceptance of equipment at site, at rates at which these are being supplied by him to other customers & also should match prices of original manufactures of these components prevailing at the time.
- (iv) If at any stage, during next 10 years, the manufacturer stops production of this model of equipment , he shall intimate All India Radio in advance to enable the later to stock the critical items.

4.0 INSPECTION AT MANUFACTURER'S WORKS:

ANNEXURE-'I'

1.0 INSPECTION DETAILS AT MANUFACTURE WORKS

The inspection for acceptance of the 16 panel Four Bay FM Antenna, RF cable , and rigid lines will be carried out at the Works of the Manufacturer in accordance with Acceptance Test Procedure (ATP).

All facilities like complete set of measuring instruments, power supply, manual assistance, etc. will be provided by the supplier without any additional charges. Inspection will be as per Specification. Engineers of All India Radio will carry out detailed inspection at manufacturers works.

The manufacturer shall put up the 16 panel Four Bay FM Antenna, RF cable , and rigid lines, for test on the test bench at manufacturers works before the representatives and shall provide without any extra charges electric energy, consumable materials, tools, testing instruments, labour and assistance of every kind for carrying out acceptance tests.

The inspection shall be carried out by the AIR Engineers. The inspection period shall be 2 working days at the manufacturer works. Complete details and specifications of Supply part of SETC i.e. 16 panel VHF FM Antenna , RF cable and rigid lines etc. will be checked and the parameter values will be measured.

The complete Acceptance Test Procedure (ATP) will be prepared by the manufacturer and submitted to Indentor for approval. This Procedure after modification (if required during the process of approval) shall form the basis for Performance/Inspection Tests to be carried out. ATP will also indicate full details of set up for measuring/testing equipment to be deployed during the Performance Measurement/ Inspection Test at factory.

Operation checking of the 16 panel VHF FM Antenna and measurements will be carried out at any three frequencies in the VHF band, 88 to 108 MHz. Complete set of instruments will be made available in advance and the list of these measuring instruments along with their set ups may be forwarded along with the Tender.

Exhaustive checking/measurements will be carried out so as to completely check the compliance of the 16 panel VHF FM Antenna , RF cable and RF rigid lines with the requirements and as per the order.

It is mandatory that all these checking and measurements i. e. Operation checking at any three frequencies in the VHF band, 88 to 108 MHz, are carried out well in

advance and these measurements details, graphical printout notes and figures must be available, at the factory at the time of inspection.

These must also be submitted to All India Radio alongwith the call for inspection well in advance for analyzing etc. 16 panel VHF FM Antenna, RF cable , RF rigid lines will be tested for 24 hours of continuous operation on full rated power output.

Following information should also form part of above data which will also be checked for 16 panel VHF FM Antenna , RF cable and RF rigid lines with the requirements and as per the order during inspection by indenter's representative at manufacturer's works :-

1. Make , type , model no and country of origin of equipment Antenna , Accessories and spares and other items /equipment.
2. Dimension of Sub-Units and Accessories.
3. Working/operation of all Sub-Units and Accessories.
4. System configuration check and completeness of 16 panel VHF FM Antenna, RF cable and rigid lines and other items /equipment
6. Checking meter readings and calibration.
7. Measurements of all parameters as per AIR specification . All the parameters will be measured on any 3 different frequencies in VHF FM band.
8. Checking of all power levels, meters, LEDs etc.
9. Checking of RF voltages on test points.

INSPECTION:

Contractor shall quote charges for Inspection at manufacturer's works by two AIR Engineers for 2 working days in respect of all equipment/items of Section 1.0 and 5.0 of AIR Specification

S.No.	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
	Charges for inspection at manufacturer's works by two AIR Engineers for 2 working days in respect of 16 panel VHF FM Antenna, RF Cable , RF Rigid Lines & Accessories			each	
1.	Silchar	1 no		each	

Section 4.0 (page no 22 to 24)
TOTAL AMOUNT: (In figures

Signature of Contractor with date and seal
Full Name in CAPITAL LETTERS:

(PURCHASE SECTION)
P & D UNIT, DG:AIR

SECTION 5.0 SCHEDULE OF (SUPPLY)

SECTION 5.1 Schedule of Supply at Silchar .

SNo.	DESCRIPTION	Qty	RATE	UNIT	AMOUNT
1.0	16 Panel VHF FM (Band II) Complete Antenna System in conformity of Section 3.1 of AIR Specification mainly comprising of the following (but not excluding other features deemed necessary)	1 complete system		Set/ System	
1.1	Power Divider (As per design of manufacturer)				
1.2	Distribution Cables (As per design of manufacturer)				
1.3	Rigid line 3 1/8" EIA with complete accessories (As per design of manufacturer)				
1.4	Instruction books (As per Specification)				
1.5	Panel reflectors (As per design of manufacturer)				
1.6	Dipoles, Horizontal (As per design of manufacturer)				
1.7	Dipoles, Vertical (As per design of manufacturer)				
1 . 8	Any other item / hardware etc. offered for the completeness of the above antenna system - 1 lot (Item wise details of the offered item / hardware etc. shall be given by the tenderer	1 lot			

SNo.	DESCRIPTION	Qty	RATE	UNIT	AMOUNT
2	RF coaxial Feeder Cable air di-electric of size 3- 1/8" as per Section 3.2 of AIR Specification. *Actual length will be intimated at the time of placement of order. (The following accessories are to be included as part of RF Feeder cable)	160 M *		M	
	2.1 3-1/8" EIA flange connectors	2 nos.		each	
	2.2 3-1/8" EIA flange Gas Pass connector	1 no.		each	
	2.3 Hoisting stockings (1 Set)for each 160 M cable as per recommendation of manufacturer	2 set		set	
	2.4 Earthing kits, (I Set Shall be with 3nos of earthing kits)	1 set		each	
	2.5 Wall gland/ feed through assembly with accessories	2 no.		each	
	2.6 Cable clamps with nut, bolt washer(adjustable width) (Suitable for two RF cables)	160 sets		Set	
	2.7 Any other accessories offered for the completeness of the system	1 lot		lot	
3	Dehydrator with tubing and accessories as per antenna manufacturer's recommendation for ensuring required Pressurisation in entire chain (to be supplied each for supplying dry air for Pressurisation of RF feeder cable and Antenna system.)	1 no		each	

SNo.	DESCRIPTION	Qty	RATE	UNIT	AMOUNT
4.	Any other accessories offered for the completeness of the system (Items wise details of offered and included material , items & part are to be given by the Tenderer).[After taking into consideration the Note given in Section 3.3 on page 21]	1 Lot		lot	
	TOTAL				

SECTION 5.1 Schedule of Supply at Silchar (page number 25 to 27)

TOTAL AMOUNT: (In figures and words)

Signature of tenderer with date and seal

Full Name in CAPITAL LETTERS:

(PURCHASE SECTION)

P & D UNIT, DG:AIR

SECTION 5.0 SCHEDULE OF SUPPLY (OPTIONAL)

SECTION 5.1 Schedule of supply at Silchar (OPTIONAL)

SNo.	DESCRIPTION	Qty	RATE	UNIT	AMOUNT
1.0	Complete erection material {RF Rigid lines & accessories as per Section 3.3 of AIR Specification as given below				
1.1	3-1/8" rigid line	6 M		M	
1.2	3-1/8" elbows with inner and bullets	6 nos.		each	
1.3	3-1/8" couplings with inner and bullets	6nos.		each	
1.4	3-1/8" field flange with inners and bullets	1 no.		each	
1.5	3-1/8" to N test reducer	1 no.		each	
1.6	3-1/8" to 1-5/8" reducer/adopter	1 no.		each	
1.7	1-5/8" to 7/8" reducer/adopter	1 no.		each	
1.8	1-5/8" rigid line	6 M		M	
1.9	1-5/8" elbows with inner and bullets	6 nos.		each	
1.10	1-5/8" couplings with inner and bullets	6 nos.		each	
1.11	1-5/8" to N test reducer	1 no.		each	
1.12	Training at site for 3 working days (optional)	1 Job		1Job	
	TOTAL				

SECTION 5.1 Schedule of Supply at Silchar (page number 25 to 28) (OPTIONAL)

Signature of tenderer with date and seal
Full Name in CAPITAL LETTERS:

**(PURCHASE SECTION)
P & D UNIT, DG:AIR**

SECTION 6.0 SCHEDULE OF ERECTION, TESTING & COMMISSIONING

SECTION 6.1 {Schedule of erection, testing & commissioning of 16 panel VHF FM Antenna, RF

cable, Antenna switch panel/frame & RF Rigid Lines & Accessories } at Silchar .

S No.	Description	Qty.	Rate	Unit	Amount
1	<p>(New Erection) Erection, testing and commissioning of 16 panel VHF FM antenna as per specification on the existing tower in the FM aperture after unpacking, physical checking/necessary care for the safety of the antenna system like cleaning, ingress of moisture pressurisation etc. at site before Erection in accordance with the Erection manual of the manufacturer along with hauling of the complete panel antenna system alongwith reflectors ,power dividers, distributor feed cables complete, as per requirement at site.</p> <p>(Existing TV tower height 150 M)</p>	One job		job	
S No.	Description	Qty.	Rate	Unit	Amount
2	<p>2.1 Erection, testing and commissioning of new 3-1/8" RF co-axial cables as per specification on the existing tower including modification/ fabrication of the cable tray as per drawing for the horizontal</p>	One job		job	

	/ vertical portion alongwith supply of complete hardware material and accessories etc. complete as required at site (Existing TV tower height 150 M)				
	2.2 Erection, testing and commissioning of new Dehydrators with tubing and accessories including making pressurisation connections etc. as per specification / manufacture's recommendations complete as required at site.	1job		job	
3	Horizontal tray including protecting of MS canopy , rate per meter shall be quoted by the tenderer. (tentative quantity, however actual quantity in running length shall be paid to the tenderer by the indentor).	20 M		M	
4	Erection, testing, commissioning of RF rigid lines interconnections of RF chain in the existing transmitter hall including placement, fixing, with the transmitter , antenna switch frame/panel along with fixing of necessary hardware in the systems complete as per site requirement as required.				
4.1	3-1/8" rigid line	12 M		M	
4.2	3-1/8" elbows with inner and bullets	12 nos.		each	
4.3	3-1/8" couplings with inner and bullets	20nos.		each	

4.4	3-1/8" field flange with inners and bullets	2 nos.		each	
4.5	3-1/8" to N test reducer	1 no.		each	
4.6	3-1/8" to 1-5/8" reducer/adopter	2 nos.		each	
4.7	1-5/8" to 7/8" reducer/adopter	2 nos.		each	
4.8	1-5/8" rigid line	6 M		M	
4.9	1-5/8" elbows with inner and bullets	6 nos.		each	
4.10	1-5/8" couplings with inner and bullets	20 nos.		each	
4.11	1-5/8" to N test reducer	1 no.		each	
4 1 2	3-1/8" to 4-1/2" reducer adopter	4 nos		each	
4 . 1 3	Any other accessories offered for the completeness - 1 Lot of the system (Items wise details of offered and included material , items & part are to be given by the tenderer)	1job		job	
5 .	Checking of complete set up as above before application of RF power and recording the test and measurement values in the form of graphical printout for necessary reference as per specification technical parameters.	One job		job	
6 .	Testing of the complete RF chain on full RF power with transmitter on the newly installed RF cable and 16 panel VHF FM antenna in the entire frequency range of 88 -108MHz.	One job		job	

S No.	Description	Qty.	Rate	Unit	Amount
7	Final performance measurements of the complete RF chain i.e. RF cable, 16 panel antenna as per specification alongwith graphical printouts of the measurements like VSWR/return-loss - for entire frequency range of 88 MHz to 108 MHz, isolation, horizontal/vertical pattern circulatory for omni-directional pattern. Actual F.S. pattern upto the signal strength of 48 dBu. Including actual F.S. pattern upto the signal strength for 54 dBu, 66 dBu & 74dBu.	One job		job	
8	Earthing of complete set up as per manufacturer recommendations.(Earthing kits for each RF cable are to be provided at different locations and complete earthing work shall be as per either manufacturer recommendation or as per AIR drawing TM - 15108/2 and TM-15175/2.(As per actual requirement at site)	Three jobs.		job	
	TOTAL				

TOTAL AMOUNT: (In figures and words)

Note : 1) The tenderer shall take up the work at **Silchar** in co-ordination/consultation with the concerned Superintending Engineer/Station Engineer, AIR & Doordarshan, and the Chief Engineer(EZ), Project Wing and Maintenance Wing.

2)The Erection, testing & Commissioning work shall be carried out at site probably during the night hours from 0.00 hrs. to 05.30 hrs. after getting the written permission of the competent authority for the start of work in accordance with the terms and conditions mentioned in the permission issued by AIR Dte./ Doordarshan Dte.

3) Tenderer is required to take into consideration the aspect of the constraint in the time made available by the AIR for the Erection, testing& Commissioning work at the site as above and the job is required to be completed in the stipulated and scheduled time frame as given in the permission, as above.

4)16 Panel VHF FM antenna, RF coaxial cables including Dehydrator with tubing and accessories and RF coaxial rigid lines will be part of supply to be arranged by the tenderer as per specification.

5) The quantities mentioned in Section 6.0 of AIR Specification *erection, testing and commissioning* are as per the tentative requirement anticipated .

6) The quantities mentioned in the schedule of requirement of *erection, testing and commissioning* in SECTION 6.0 may *increase or decrease* as per site requirement. However payment will be made to the tenderer *as per actual quantity used /erected at site after satisfactory completion of work* .

Tenderer *shall quote the rates per meter length /per number / per job* in respect of erection, testing and commissioning,

SECTION 6.0 SCHEDULE OF ERECTION, TESTING & COMMISSIONING

**SECTION 6.1 Schedule of erection, testing & commissioning { of 16 panel VHF FM Antenna, RF Cable, Antenna switch panel/frame , RF Rigid Lines & Accessories } at Silchar
(page number 29 to 33)**

Signature of tenderer with date and seal
Full Name in CAPITAL LETTERS:

**(PURCHASE SECTION)
P & D UNIT, DG :AIR**

This site is maintained by All India Radio.